

Comune di:
Provincia di:

pag. 1

COMPUTO METRICO

OGGETTO:

COMMITTENTE:

Data, _____

IL TECNICO

Num.Ord. TARIFFA	DESIGNAZIONE DEI LAVORI	DIMENSIONI				Quantità	IMPORTI	
		par.ug.	lung.	larg.	H/peso		unitario	TOTALE
	R I P O R T O							
	<u>LAVORI A MISURA</u>							
1 800.002	Fornitura e posa di tubi in Polietilene PE DN 110 SPIG Pipe_ DN 110_ SPIG (IdEnt: -0)					7,000		
	SOMMANO m					7,000	69,13	483,91
2 800.004	Fornitura e posa di tubi in Concrete 1500 x 1000 Egg- Shaped Culvert SI							
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909f5e0)		6,278			6,278		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909e45b)		8,431			8,431		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909e474)		9,565			9,565		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909e4f1)		16,342			16,342		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909e513)		24,841			24,841		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909f673)		41,658			41,658		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909f63c)		41,137			41,137		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909f0a4)		8,679			8,679		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909f82b)		7,155			7,155		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909f080)		33,428			33,428		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909e52c)		13,399			13,399		
	Concrete Egg-Shaped Culvert SI - (IdEnt: 909f053)		24,852			24,852		
	SOMMANO m					235,765	50,00	11 ' 788,25
3 900.004	Fornitura e posa di pozzetti Concentric Cylindrical Structure SI DN 1500 compreso chiusino o griglia Concentric Cylindrical Structure SI (IdEnt: -19)					10,000		
	SOMMANO cad.uno					10,000	6 ' 000,00	60 ' 000,00
4 900.005	Fornitura e posa di pozzetti Rectangular Structure Slab Top Rectangular Frame SI 750 x 1500 compreso chiusino o griglia Rectangular Structure Slab Top Rectangular Frame SI (IdEnt: -29)					16,000		
	SOMMANO cad.uno					16,000	250,00	4 ' 000,00
5 900.007	Fornitura e posa di Tee DN 150 BW Rete Gas (IdEnt: 90a009d) (IdEnt: 90a00aa) (IdEnt: 90a00ac) (IdEnt: 90a00ce)		22,236 46,484 0,832 100,955			22,236 46,484 0,832 100,955		
	SOMMANO m					170,507	65,43	11 ' 156,27
6 NP 001	Scavo Scavo - (IdEnt: 90a00ce) *(lung.=100,955*1,2) Scavo - (IdEnt: 90a009d) *(lung.=22,236*1,2) Scavo - (IdEnt: 90a00ac) *(lung.=0,832*1,2) Scavo - (IdEnt: 90a00aa) *(lung.=46,484*1,2)		121,146 26,683 0,998 55,781	2,000 2,000 2,000 2,000	3,000 3,000 3,000 3,000	726,876 160,098 5,988 334,686		
	SOMMANO m3					1 ' 227,648	10,00	12 ' 276,48
7 NP 002	Smantellamento vecchia rete Smantellamento Rete Distribuzione Gas - (IdEnt: 90a00aa) Smantellamento Rete Distribuzione Gas - (IdEnt: 90a00ce)		46,484 100,955			46,484 100,955		
	A R I P O R T A R E					147,439		99 ' 704,91

COMMITTENTE:

